



August 5, 2024

Re: Addendum No. 1 – 2024 Hamilton Road Pier Wall Project

Dear Prospective Bidder:

Listed below is Addendum No. 1 for the referenced project. Please note the following clarifications/modifications to be included in your bid price. The bid opening for this project will remain as scheduled Wednesday, August 14, 2024, at 9:30 am at the Warren County Commissioners, 406 Justice Drive, Lebanon, Ohio 45036.

ADDENDUM NO. 1

1. Clarification/Modification: (Plans and Specifications)

As per the technical specifications, the Armormax 75 shall only be installed from the edge of the proposed pier wall to 30 feet from the center of the road, as these are the limits of the right-of-way. Do not disturb the fence on the east side of the roadway, which is outside of the right-of-way. The plans do not show this correctly, so please install the Armormax 75 based on this statement.

2. Clarification/Modification: (Technical Specifications)

Please see below for added item on the technical specifications.

Item 832 – Erosion Control

The Contractor shall furnish and install temporary sediment and erosion control best management practices required prior to any earth disturbing activity in accordance with Supplemental Specification 832. All pollution prevention measures must be maintained for the duration of construction. Silt fence will be required, extending over the entire length of the pier wall. The Contractor shall remove all best management practices before the project is accepted. Payment for this work shall follow Supplemental Specification 832 and will be included in the bid price per Each for Item 832 Erosion Control. This price is standard for all bidders, set at \$1.00 Each for a total of \$1,000.00 total.

3. Clarification/Modification: (Bid Proposal)

Please remove existing Bid Proposal and use the attached updated Bid Proposal when submitting your bid.

WARREN COUNTY ENGINEER'S OFFICE

ADMINISTRATION and ENGINEERING
210 W Main St. Lebanon, OH 45036
Telephone (513) 695-3301 Fax (513) 695-7714

HIGHWAY MAINTENANCE, PERMITS, and INSPECTION
105 Markey Rd. Lebanon, OH 45036
Telephone (513) 695-3336 Fax (513) 695-3323

Addendum No. 1 shall be signed and included with the submission of the bid. Please sign below and enter the date you received this addendum. **Any bid submitted without the signed Addendum No. 1 shall be rejected.** If you have any questions, please call me at 513-695-3318.

Sincerely,

Neil F. Tunison, P.E., P.S.
WARREN COUNTY ENGINEER



Logan Smith, E.I.
Project Engineer

Received by

Signature

Company

Date

cc: file

BID PROPOSAL – cont.

Proposal for the drilled pier wall and roadway work on Hamilton Road. This work consists of constructing the drilled pier wall and the related items for the 2024 Hamilton Road Drilled Pier Wall Project. The drilled pier wall project shall be as per plans and specifications as provided by the Warren County Engineer.

The undersigned do hereby propose to furnish all labor, materials, tools, equipment, etc., necessary to construct this project for the Warren County Engineer’s Office. The above quotations to be in full force and effect for sixty (60) days after the date of opening bids. The full name and address of all persons and parties interested in the foregoing bids as principals are as follows:

Total Bid Price \$ _____

The contract will be awarded to the best and most responsive bid based on the qualifications of the Contractor and the total price of the Total Bid.

SIGNED

PRESIDENT

COMPANY

SECRETARY

BY

TITLE

DATE

ADDRESS

**2024 HAMILTON ROAD DRILLED PIER WALL PROJECT
 BID PROPOSAL**

Item No.	Description	Quantity	Unit	Unit Cost	Total Cost
	Hamilton Road				
201	Clearing and Grubbing	1	Lump		
202	Guardrail Removed	275	FT		
203	Excavation	27	CY		
204	Subgrade Compaction	54	SY		
301	Asphalt Concrete Base PG 64-22	30	Ton		
304	Aggregate Base	14	CY		
441	Asphalt Concrete Surface Course, Type 1, (448), PG 64-22	6	Ton		
524	Drilled Shafts, 30" Diameter, Unreinforced	672	FT		
524	Drilled Shafts, 30" Diameter, Reinforced	496	FT		
606	Guardrail, Type 5	275	FT		
614	Maintaining Traffic	1	Lump		
623	Construction Layout Stakes and Surveying	1	Lump		
624	Mobilization	1	Lump		
626	Barrier Reflector, Type 2A	6	Each		
630	Removal of Ground Mounted Sign and Reset	1	Each		
642	Edge Line, 4 inch, Type 1	0.03	Mile		
659	Seeding and Mulching	80	SY		
832	Erosion Control	1	Each	\$ 1,000.00	\$1,000.00
Special	Armormax 75	1	Lump		
				Sub-Total =	